



Structural Systems

ANCHOR INSTALLATION COMPLETE AT CATAGUNYA DAM



The final anchors have now been installed and grouted at Catagunya Dam in Tasmania.

This concludes the manufacture, install and grouting phase of the project, involving 91 No. 91x15.7mm and 1 No. 36x15.7mm permanent anchors.

Some 5.5km of anchors, utilised nearly 700t of strand, 527km of poly pipe, 40t of grease and 32,000 bags of cement.

This is only the second time that 91 strand anchors have been utilised in the world, previously by ourselves at Canning Dam in 2000.

The Catagunya project has been an outstanding success so far, with only stressing and sealing of the 51 spillway anchors left to complete.

